




**Australian Government**  
**Civil Aviation Safety Authority**



# Baro-VNAV flight validation


Presented by Steven Kreusser (Aviation Safety Inspector)

# Registered Aerodromes






# Controlled Airspace




# Flight Validation – Why?



- » Lack of ICAO compliant obstacle data - no eTOD
- » Lack of mature AIM process
- » Aerodrome remoteness
- » Airspace/Approach complexity
- » Flyability




# Airspace / Approach complexity



- » All OCTA – no airspace
- » 12 aerodromes
- » 200nm across
- » Procedures designed to be separated. Not always possible.
- » Exemptions required

# Flight Validation – Koolan Island




- » New runway
- » Runway surface extracted from surrounding mine
- » Detailed topographic information not available
- » LNAV + LNAV/VNAV



# Flight Validation – Koolan Island



# Flight Validation – Koolan Island





# Flight Validation – Koolan Island



# What information did we have?

## Aerodrome survey


Koolan Island Central - Aerodrome Survey										Date	26/06/2020	
Position		160733S		1234405E		Elevation		538 FT				
Note ARP may vary slightly to ERSA due to rounding.												
Runway Details		Dimensions		2100 m x 30 m		Slope		0.34% down to E		Surface Sealed		
		Levels TKOF 11		RWY END		156.396		TKOF 29 RWY END		163.637		
		RWS END		155.866				RWS END		163.418		
Declared Distances							Survey Specs					
							Code 3 Non-Instrument					
							Take-Off SFC		Approach SFC			
RWY		TORA		TODA		ASDA		LDA				
11		2100		2160 (1.87%)		2100		2100				
29		2100		2160 (1.2%)		2100		2100				
Supplementary Take-Off Distances												
RWY		1.6%		1.9%		2.2%		2.5%		3.3%		
11		2076		NA		NA		NA		NA		
29		NA		NA		NA		NA		NA		
							Inner Edge		180 m		Inner Edge 150 m	
							Dist FM THR		60 m		Dist FM THR 60 m	
							Divergence		12.5%		Divergence 10%	
							Final Width		1800 m		1st Sect Slope 3.33%	
							Length		15000 m		1st Sect Length 3000 m	
Obstacle Information												
TKOF RWY	Object No	Description	DIST OUT	HT ABV CWY	OBST GRAD	OBST RL	DIST FM SOT	OFFSET	Comment			
11	1	Tree	2249.56 m	26.27 m	1.16%	182.67 m	4409.56 m	417.61 mL	Outside TKOF SFC			
11	2	Tree	570.83 m	8.31 m	1.45%	164.71 m	2730.83 m	49.77 mR				
11	3	Tree	566.35 m	8.65 m	1.52%	165.05 m	2726.35 m	43.24 mR				
11	4	Tree	592.11 m	10.75 m	1.81%	167.14 m	2752.11 m	102.98 mR				
11	5	Tree	587.19 m	11.02 m	1.87%	167.41 m	2747.19 m	132.68 mR	Critical Object			
11	6	Tree	607.49 m	11.16 m	1.83%	167.55 m	2767.49 m	133.56 mR				
11	7	Tree	489.63 m	9.19 m	1.87%	165.59 m	2649.63 m	186.64 mR	Outside TKOF SFC			
11	8	Dome	913.83 m	9.88 m	1.08%	166.28 m	3073.83 m	73.4 mR				
11	9	Dome Antenna	924.86 m	11.63 m	1.25%	168.02 m	3084.86 m	68.1 mR				
29	No Objects Surveyed											

Note: No datum, or threshold coordinates



# What information did we have?

## Lidar topographic survey



Note: No vertical or horizontal datum

# Conclusion – Flight Validation required

Typically we use C-441 conquest





# Conclusion – Flight Validation required

....sometimes we use a Beechcraft Baron



# Information required for flight validation

- » Waypoint and obstacle coordinates for GPS




Waypoint and obstacle information is manually loaded into GPS navigator. This allows us to check bearings and distance of procedure legs and cross check position of controlling obstacles.



All data loaded in EFB using KML files. This allows accurate navigation for protection areas and sloped surfaces.

# Information required for flight validation

» Contoured FAS and VSS



Contours are used to validate the controlling surfaces, and check controlling obstacles.

These surfaces are flown.



# Information required for flight validation

## » Complete Obstacle list

AERODROME: YKLC OBSTACLES											
	Serial	Segment	Description	BRG °T	Dist (KM)	Dist (NM)	Elev (ft)	MOC	Nominal Alt (ft)	OIS / Fit Alt (ft)	Approximate Position
MSA	KLC001	10NM	TERRAIN	178°	6.91	3.73	901	1000	2000	1000	16 11.28 123 44.22
MSA	KLC002	25NM	TERRAIN	138°	54.60	29.48	1235	1000	2300	1300	16 29.51 124 4.570
RNAV (GNSS) RWY11	KLC004	HOLDING	TERRAIN	286°	21.64	11.69	645	984	2300	1316	16 4.402 123 32.39
RNAV (GNSS) RWY11	KLC004	RIGHT INITIAL	TERRAIN	286°	21.64	11.69	645	984	1700	716	16 4.402 123 32.39
RNAV (GNSS) RWY11	KLC005	CENTRE INITIAL	TERRAIN	294°	24.56	13.26	474	984	1700	716	16 2.259 123 31.45
RNAV (GNSS) RWY11	KLC006	LEFT INITIAL	TERRAIN	294°	22.10	11.93	317	984	1700	716	16 2.611 123 32.80
RNAV (GNSS) RWY11	KLC007	INTERMEDIATE	TERRAIN	286°	20.92	11.30	573	492	1100	608	16 4.53 123 32.78
RNAV (GNSS) RWY11	KLC008	FINAL	RW11 THR+100FT	300°	1.09	0.59	637	246	890	644	16 7.263 123 43.57
RNAV (GNSS) RWY11	KLC008	INITIAL MISSED LNAV	RW11 THR+100FT	300°	1.09	0.59	637	246	890	644	16 7.263 123 43.57
RNAV (GNSS) RWY11 LNAV/VNAV	KLC008	FINAL LNAV/VNAV	RW11 THR+100FT	300°	1.09	0.59	637	161	820	659	16 7.263 123 43.57
RNAV (GNSS) RWY11 LNAV/VNAV	KLC009	INITIAL MISSED LNAV/VNAV	TERRAIN	131°	0.55	0.30	638			638	16 7.752 123 44.33
RNAV (GNSS) RWY11	KLC010	COMMON MISSED	TERRAIN	100°	5.07	2.74	625	164		931	16 8.049 123 46.90
RNAV (GNSS) RWY29	KLC011	LEFT INITIAL	TERRAIN	130°	23.44	12.66	681	984	1700	716	16 15.74 123 54.14
RNAV (GNSS) RWY29	KLC012	CENTRE INITIAL	TERRAIN	119°	27.03	14.59	635	984	1700	716	16 14.66 123 57.36
RNAV (GNSS) RWY29	KLC013	RIGHT INITIAL	TERRAIN	112°	17.94	9.69	287	984	1700	716	16 11.20 123 53.44
RNAV (GNSS) RWY29	KLC014	INTERMEDIATE	TERRAIN	124°	13.48	7.28	438	443	1100	657	16 11.66 123 50.35
RNAV (GNSS) RWY29	KLC003	FINAL	TERRAIN	102°	3.41	1.84	710	246	960	714	16 7.956 123 45.96
RNAV (GNSS) RWY29	KLC015	INITIAL MISSED	TERRAIN	129°	0.57	0.31	638	246	960	714	16 7.752 123 44.35
RNAV (GNSS) RWY29 LNAV/VNAV	KLC003	FINAL LNAV/VNAV	TERRAIN	102°	3.41	1.84	710	161	880	See FAS contours	16 7.956 123 45.96
RNAV (GNSS) RWY29 LNAV/VNAV	KLC016	INITIAL MISSED LNAV/VNAV	TERRAIN	295°	0.56	0.30	602			602	16 7.431 123 43.81
RNAV (GNSS) RWY29	KLC017	COMMON MISSED	TERRAIN	290°	5.17	2.79	510	164		1045	16 6.585 123 41.37
RNAV (GNSS) RWY29	KLC018	HOLDING	TERRAIN	119°	40.26	21.74	1091	984	2300	1316	16 17.98 124 3.919
CIRCLING	KLC003	CAT A/B	TERRAIN	102°	3.41	1.84	710	295	1040	745	16 7.956 123 45.96
CIRCLING	KLC003	CAT C	TERRAIN	102°	3.41	1.84	710	394	1140	746	16 7.956 123 45.96
CIRCLING	KLC003	CAT D	TERRAIN	102°	3.41	1.84	710	394	1230	836	16 7.956 123 45.96

Time to go and fly!



# Remember this?



# Now this






# View from other end




# What was flown?





# Compared to procedure design splays



# VSS check


VSS intercept distance(NM) from MAPT at Final Segment Check Altitude			
VSS intercepts final segment check altitude of	644	FT at	0.57 NM from MAPT
VSS intercepts final segment check altitude of	714	FT at	1.04 NM from MAPT



# FAS check

On site flight validation: Example profile – Baro-VNAV FAS Check

- Descent managed using EFB overlayed altitude contours (hand flown) with aircraft position reference





# Threshold check

YKLC	KOOLAN CENTRAL		
Runway 11	16° 07.26' S	123° 43.57' E	537FT
Runway 29	16° 07.74' S	123° 44 .64 E	513FT



# Time to fly back to the office



# Post flight validation

ED BY MFO  
N 3.0  
D

## FLIGHT VALIDATION REPORT

### KOOLAN CENTRAL (YKLC)

Date:	11-Sep-20	Aircraft Registration:	VH-VEY
Validation Pilot:	Alf Jonas	A.P. Jonas, MFO, 17 Sep 2020	
Validation Observer:	Simon Ozanne	L	
Procedure Designer:	Tim Thorn	Tim Thorn Digitally signed by Tim Thorn Date: 2020.09.18 13:58:06 +1000	

### CERTIFICATION

The aerodrome is currently UNCERTIFIED.

The specified altitudes of the mentioned instrument approach/arrival procedures have been checked and the procedures are acceptable subject to the mentioned changes (if any) being incorporated.

The mentioned instrument procedures are suitable for straight-in minima.

Aerodrome lighting systems were not able to be assessed. (See comments)

The WDI is suitable for straight-in minima to all RWYs.

The suitable WDI is illuminated.

The (re)validation was conducted between 110131Z and 110257Z SEP 20.

The minimum number of satellites available and average HFOM during that period was 8 and 22 feet respectively. RAIM was continuously available.

Meters were checked/reset on the threshold of RWY 11 : elevation 537 AMSL.

### INFRASTRUCTURE VERIFICATION

RWY	Threshold Coordinates	APP Lighting	Suitability - APP Lighting
Y 11	S16 07.26 E123 43.57	PAPI	Not able to be assessed (See Comments)
Y 29	S16 07.74 E123 44.64	PAPI	Not able to be assessed (See Comments)

### COMMENTS

- Aerodrome lighting (at 60m spacing), PAPI and illuminated WDI are all located as depicted on the Aerodrome Facilities Plan and the draft ERSA entry. Lighting not operational at time of validation and therefore not assessed.
- AWIS not operational at time of validation.
- Designer provided Baro VNAV FAS contours assessed. FAS penetrations are consistent with the location of the controlling terrain points KLC008 (RWY 11) and KLC003 (RWY 29). Baro VNAV procedure sim validation (flyability and coding) required prior to publication.
- The Telstra comms tower (reported elevation of 701') in the final segment and at 1.34nm SE of RWY29 THR is not erected. Buffered terrain assessment, which is 9' high than the comms tower, remains controlling.
- Recommend including a Local Traffic Regulation in the ERSA FAC entry regarding high-density VFR operations within 5nm of Talbot Bay / Horizontal Falls and that special procedures apply (as per ERSA GEN - SP) in this area.

### PREVIOUSLY UNIDENTIFIED OBSTACLES

Description	Approx. Elevation	Location	Owner (If Known)
None			

### COMMON SEGMENTS


SEGMENT	COMMENTS	NEED for CHANGE
25 MSA	SATISFACTORY	
10 MSA	SATISFACTORY	
Circling	SATISFACTORY	
VSS / VAA	SATISFACTORY	

### INSTRUMENT APPROACH PROCEDURES

PROCEDURE	SEGMENT	COMMENTS	NEED for CHANGE
RNAV (GNSS) RWY 11 (DRAFT)	Holding	SATISFACTORY	
	Left Initial	SATISFACTORY	
	Centre Initial	SATISFACTORY	
	Right Initial	SATISFACTORY	
	Intermediate	SATISFACTORY	
RNAV (GNSS) RWY 29 (DRAFT)	Final	SATISFACTORY	
	Missed Approach	SATISFACTORY	
	Holding	SATISFACTORY	
	Left Initial	SATISFACTORY	
	Centre Initial	SATISFACTORY	
	Right Initial	SATISFACTORY	
	Intermediate	SATISFACTORY	
	Final	SATISFACTORY	
	Missed Approach	SATISFACTORY	



# Extreme Flight Validation Wilkins Aerodrome Antarctica



# Extreme Flight Validation Wilkins Aerodrome Antarctica



# Extreme Flight Validation Wilkins Aerodrome Antarctica





Thank You