

CNS SG/18 – IP/23 Agenda Item 7 (2) 21/07/14

SUMMARY

This briefing paper describes the current state of the ground

surveillance facilities installed in Incheon International Airport

(hereinafter referred to as IIA); suggests how to solve problems that

occurred as a result of the operation; presents the future plan of the IIA

for the enhanced ground surveillance.





1. INTRODUCTION

- Currently, IIA is operating Ku-band (since 2000), X-band and ADS-B (since 2008) as ground surveillance facilities.
- IIA plans to operate and manage systems such as SMR(2 sets), ADS-B(1 set) and MLAT(1 set) in an integrated way in order to address the coupling errors caused by the ASR and ASDE target differences as well as a false target produced by snowfall and rainfall.
- IIA will change its operating system into the next generation air navigation system such as precision approach surveillance that enables simultaneous landings and takeoffs. In addition, it will strengthen the support for ground control service even under *low-visibility* conditions (with visibility minimum of 75 m) as a CATIIIb airport to achieve 400,000 times of aircraft landings and takeoffs by 2020.



2. DISCUSSION

• 2.1 The Current State and Operation Features of the IIA






ICAO Regional Sub-Office, Beijing, China (21-25 July 2014)

Classification	Installation Year	Operation Features
Ku-Band SMR (TWR)	2000	 Performance under rainfall : occurrence of false target (at 16 mm/hr or more) Performance under snowfall : occurrence of False target Shadow zone : Terminal
X-Band SMR (RAMP TWR)	2008	 Performance under rainfall: Usable (at 40mm/hr or under) Performance under snowfall: occurrence of False target Shadow zone : Terminal area
ADS-B	2008	 ADS-B installation rate on aircrafts : about 40% No auto-labeling that distinguishes landings from takeoffs Transmission of the data that indicates a coupling error for some uncertified aircrafts
Fusion processer	2008	 De-couplings for some aircrafts Position errors caused by differences between the ASR and ASDE targets



problems that occurred as a result of the operation

Shadow zone Created by limited line of sight





ICAO Regional Sub-Office, Beijing, China (21-25 July 2014)

problems that occurred as a result of the operation









problems that occurred as a result of the operation

False target produced by the reflection of snowbanks and ice formation





problems that occurred as a result of the operation


Label Drop caused by different position reports between ASR and SMR targets





ICAO Regional Sub-Office, Beijing, China (21-25 July 2014)








ICAO Regional Sub-Office, Beijing, China (21-25 July 2014)


problems that occurred as a result of the operation





ICAO Regional Sub-Office, Beijing, China (21-25 July 2014)

PAL491





2.2 How to Develop and Improve ground surveillance facilities

- System realization regardless of meteorological conditions such as rainfall and snowfall
- System realization that is easy to extend detection zones
- Backup system realization that enables a single operation (operate independently)
- Enhancement of the existing ground surveillance facilities by diversifying detection facilities
- Changeover to the next generation air navigation system (FINAL GOAL)




MLAT(Multilateration) Concept



Transponder signal reception from more than 3 ground sensors Aircraft position identification by using TDOA (different time of arrivals) Mode A/C and Mode S availability




The 3rd Phase Incheon International Airport Facilities layout





The 3rd Phase Incheon International Airport Facilities layout





Comparison between the Existing and the Improved Systems after the System Enhancement

Classification	The existing system	The improved system
Detection facilities diversification	SMR (2 sets)+ADS-B (1set)	SMR (2 sets) +ADS-B (1 set) +MLAT (1 set)
Meteorological Conditions	Related	Unrelated
Back-up system	None	possible
Wake detection	Some Label Drops	100% detection
Shadow zone	many	None
Auto-Labelling	Departure(manual),Arrival(Automatic)	Automatic
Resolution	24m	7.5m



Promotion plan

Facilities	Installation plan	Budget	Note
MLAT	2017	5 billion (KRW)	The Third Phase Construction Project
X-band	2017	3 billion (KRW)	The First Phase Improvement Project (in Replacement of Ku-Band, including the Data Fusion Processor)